

TUMKUR DIVISION.

The 13th June 1899.

Tenders are hereby invited for restoring Agrahara tank, Registered No. 6, Koratagere sub-taluk.

2. The plans, detailed estimates, and conditions may be seen at the Executive Engineer's office between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor, and forwarded in sealed covers to the Executive Engineer before the 15th July 1899.

4. The final acceptance of any tender will rest with the Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 200 as earnest money.

6. Within eight days of the acceptance of the tender, the contractor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

Abstract estimate of restoring Agrahara tank, Registered No. 6 of Koratagere sub-taluk.

	Items of work.	Per	Quantity.
Bund—			
Earth-work	...	C. yds.	89,688
Old stone work	...	C. yds.	3,448
New stone work	...	C. yds.	4,083
B. M. stones	...	No.	2
Grade stones, index and bed slabs	...	No.	28
Gauge stone	...	No.	1
Register No. stone	...	No.	1
Sluice No. 1—			
Brick in chunam	...	C. ft.	1,477
Slab stones, 3" thick	...	S. ft.	393
Cutting holes in slab for plugs to work	...	Lump sum	
Chunam plastering	...	Sqrs.	5.92
Plug and rod, &c., complete	...	Lump sum	
Sluice No. 2	...	Lump sum	
Right waste weir—			
Excavation	...	C. yds.	498
Brick in chunam	...	C. ft.	3,923
Chunam plastering	...	Sqrs.	16.20
Covering slabs, 6" thick	...	S. ft.	289
New stone work	...	C. yds.	511
Left waste weir—			
Excavation	...	C. yds.	882
Brick in chunam	...	C. ft.	3,658
Chunam plastering	...	Sqrs.	15.38
Covering slabs, 6" thick	...	S. ft.	293
New stone work to apron	...	C. yds.	516
Miscellaneous—			
Deviating road in tank bed	...	Lump sum	

D. SITARAM RAO, *Exec. Engr.*

HASSAN DIVISION.

ADVERTISEMENT.

It is hereby notified for information of the public that the 2nd class travellers' bungalow at Channarayapatna is not available for occupation till further intimation, since the building is under repairs.

R. E. DAVIS,
Offg. Executive Engineer.